State of California – Natural Resources Agency
DEPARTMENT OF FISH AND WILDLIFE
Land and Facilities Engineering Branch
1010 Riverside Parkway
West Sacramento, CA 95605
Engineering@wildlife.ca.gov

GAVIN NEWSOM, Governor
MEGHAN HERTEL, Director

February 19, 2026

PLAN HOLDERS

P2599006, Addendum 2,
Green Island Unit Demolition, Napa/Sonoma Marshes Wildlife Area, Napa County

Exhibit A1 - SCOPE OF WORK CONTINUED, has been updated with the following changes:

Section F. Work Schedule:

Add the following:

Working hours shall be Monday thru Friday from 8:00 AM to 5:00 PM; excluding holidays and weekends.

F. Work Schedule

The Contractor shall furnish the Engineer with a proposed work schedule ***SEVEN (7) DAYS PRIOR TO BEGINNING WORK and*** The Contractor shall submit at such times as may be requested by the Engineer, schedules which shall show the order in which the Contractor proposes to carry on the work with dates at which the Contractor will start the several parts of the work and estimated dates of completion of the several parts.

Working hours shall be Monday thru Friday from 8:00 AM to 5:00 PM; excluding holidays and weekends.

Section M. Utility Requirements:

Add the following:

4. Two (2) CDFW poles between large warehouse and office shall be removed. See Drawings for location of poles. All other poles belong to PG&E and shall not be removed.

M. Utility Requirements

1. **Contractor shall notify 811 "Call Before You Dig" prior to mobilization.**
2. **Existing PG&E service to the Green Island Unit (State Owned Housing (SOH) and warehouse/office sites) has been disconnected at the intersection of Green Island Road and the access road. All meters have been removed.**
   a. Prior to mobilization, the contractor shall notify PG&E of the intent to start demolition of structures.
   b. Disconnected and loose conductors shall be taped and coiled at the bottom of the PG&E power poles.
3. **Existing AT&T phone line between PG&E power pole and CDFW power pole to be removed at office shall be coiled at the bottom of the PG&E power pole.**
4. **Two (2) CDFW poles between large warehouse and office shall be removed. See Drawings for location of poles. All other poles belong to PG&E and shall not be removed.**

Section N. Scope of Work:

Add the following:

j. Wind requirements shall be per Best Management Practices (BMP) and the Napa County Requirements WE-1.

k. Dust requirements will be monitored by CDFW IH consultant on site.

N. Scope of Work

1. The contractor agrees to provide to the California Department of Fish and Wildlife (CDFW) demolition and clearance services, hazardous material abatement services, Water Pollution Control Program (SWWPP) services, and implementation of said Program as described herein.

a. Contractor shall provide all labor, tools, parts, equipment, supplies, supplies, materials, permits, travel, and incidentals necessary to demolish and remove seven (7) structures and features at the Green Island Unit.

b. Abate all hazardous materials including but not limited to friable and non-friable asbestos and lead paint, according to all environmental laws and regulations, and provide any necessary SWWPP and implementation of said Program.

c. The work shall be done in accordance with all required Federal, State, and County codes/regulations.

d. Prior to demolition activity, Contractor shall be responsible for removing any hazardous waste, including, but not limited to, all friable and non-friable asbestos, lead-containing paint, mercury-containing thermostats, and fluorescent light fixtures, according to all environmental laws, regulations, and **Hazardous Materials Survey Report (Attachment 1)**.

e. The Contractor shall remove and abandon two (2) septic tanks is in compliance with Napa County governmental regulations and requirements; Drainage and Sewer Facilities Regulations. Septic tank removal shall be subject to inspection and approval by CDFW Contract Manager and respective County. The contractor shall notify the County and CDFW Contract Manager a minimum of twenty-four (24) hours prior to septic tank pumping and destruction.

f. The contractor will provide temporary perimeter fencing around demolition area as required to meet all State and County permitting, requirements, and regulations.

g. The contractor shall be responsible for developing and providing a Statewide Construction Stormwater General Permit.

h. The contractor shall grade the site to a finished grade in accordance with the approved SWWPP, or as directed by CDFW Contract Manager.

i. Contractor shall erect a temporary security fence with lockable gate at the entrance to the Green Island Unit. See Drawing Sheet 1 for location. The fence shall extend on both sides of the road to prevent foot and bicycle traffic.

j. Wind requirements shall be per Best Management Practices (BMP) and the Napa County Requirements WE-1.

k. Dust requirements will be monitored by CDFW IH consultant on site.

Section O. Detailed Description of Work:

Add the following:

Item numbering has been revised beginning after Item No. 4 to correct the omission of Item No. 5. All subsequent item numbers have been updated accordingly.

Additional sub-section added to Item No. 14 -

14. **Debris**

    c. At the completion of the demolition, Contractor shall sweep area for nails with magnetic locator.

14. **Debris**

    a. Debris shall not be disposed of on State property. The contractor shall make arrangements for disposal outside the State property.

    b. Materials to be disposed of shall not be burned either inside or outside of the State property.

    c. **At the completion of the demolition, Contractor shall sweep area for nails with magnetic locator.**

Section P. ADDITIVE #1:

Add the following:

5. The table below shall be used to calculate costs for removal of slabs and foundations.

Structure	Slab Thickness (Inches)	Perimeter Foundation Depth (Inches)	Column Footings Width x Length x Depth (Feet x Feet x Feet)
SOH Garage	6	15	N/A
Office	6	15	N/A
Warehouses	9	24	5 x 5 x 3

P. ADDITIVE #1

1. Contractor shall remove concrete foundations and miscellaneous slabs as follows:
   a. North Area
      - Garage #2 concrete slab and foundation
      - Garage #2 driveway
   b. South Area
      - Warehouse #1 concrete slab and foundation
      - Warehouse #1 miscellaneous adjoining concrete slabs
      - Warehouse #2 concrete slab and foundation
      - Office concrete slab and foundation
2. Contractor shall fill in and level areas created by excavation of concrete slabs and foundations. Material shall be from an onsite location from the North Area as directed by the Facility Manager. No outside material will be brought in or allowed.
3. The contractor shall do all excavating and leveling necessary to accomplish the demolition and removal of all slabs, footings, piers, foundation walls, and curbs.
4. Any excess material resulting from excavation shall be cleaned of foreign debris and spread on site.
5. **The table below shall be used to calculate costs for removal of slabs and foundations.**

Structure	Slab Thickness (Inches)	Perimeter Foundation Depth (Inches)	Column Footings Width x Length x Depth (Feet x Feet x Feet)
SOH Garage	6	15	N/A
Office	6	15	N/A
Warehouses	9	24	5 x 5 x 3

Please acknowledge receipt of this addendum in the space provided on the Bid Form.

Sincerely,

Robert Benson, Senior Engineer (RA)
Wildlife and Fisheries Division
Land and Facilities Engineering Branch